

Attachment A

CITY OF NAPLES / COLLIER COUNTY  
CENTRAL AVENUE IMPROVEMENTS PROJECT

BID TABULATION FORM  
BID NO. << >>

ITEM NO.	ITEM DESCRIPTION	UNIT	PROJECT QUANTITY	UNIT PRICE	AMOUNT
<b>Roadway</b>					
0101 1	MOBILIZATION	LS	1		\$0.00
0102 1	MAINTENANCE OF TRAFFIC	LS	1		\$0.00
0104 10 3	SEDIMENT BARRIER	LF	1885		\$0.00
0104 18	INLET PROTECTION SYSTEM	EA	44		\$0.00
0110 1 1	CLEARING & GRUBBING	AC	3.72		\$0.00
0110 4	REMOVAL OF EXISTING CONCRETE PAVEMENT	SY	2230		\$0.00
0120 1	REGULAR EXCAVATION	CY	3908		\$0.00
0120 6	EMBANKMENT	CY	813		\$0.00
0160 4	TYPE B STABILIZATION	SY	7547		\$0.00
0162 1 11	PREPARED SOIL LAYER, FINISH SOIL, 6"	SY	533		\$0.00
0210 1 8	REWORKING LIMEROCK BASE, 4"	SY	155		\$0.00
0285709	OPTIONAL BASE, BASE GROUP 09	SY	5104		\$0.00
0327 70 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	11693		\$0.00
0334 1 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	1205.4		\$0.00
0334 1 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B (OVERBUILD)	TN	470.6		\$0.00
0337 7 42	ASPH CONC FC, TRAFFIC B, FC-9.5, PG 76-22	TN	929.2		\$0.00
0339 1	MISC. ASPHALT PAVEMENT	TN	8.25		\$0.00
0425 1201	INLETS, CURB, TYPE 9, <10	EA	2		\$0.00
0425 1203	INLETS, CURB, TYPE 9, J BOT, <10	EA	1		\$0.00
0425 1351	INLETS, CURB, TYPE P-5, <10	EA	7		\$0.00
0425 1361	INLETS, CURB, TYPE P-6, <10	EA	7		\$0.00
0425 1362	INLETS, CURB, TYPE P-6, >10	EA	1		\$0.00
0425 1451	INLETS, CURB, TYPE J-5, <10	EA	1		\$0.00
0425 1461	INLETS, CURB, TYPE J-6, <10	EA	1		\$0.00
0425 1521	INLETS, DT BOT, TYPE C, <10'	EA	8		\$0.00
0425 1910	INLETS, CLOSED FLUME	EA	6		\$0.00
0425 2 41	MANHOLE, P-7, <10'	EA	8		\$0.00
0425 2 43	MANHOLE, P-7, PARTIAL	EA	4		\$0.00
0425 2 61	MANHOLE, P-8 <10	EA	1		\$0.00
0425 2 71	MANHOLE, J-7, <10'	EA	3		\$0.00
0425 2 73	MANHOLE, J-7, PARTIAL	EA	1		\$0.00
0425 2 93	MANHOLE, J-8, PARTIAL	EA	1		\$0.00
0430175118	PIPE CULV, OPT. MATL, ROUND 18" S/CD	LF	1791		\$0.00
0430175124	PIPE CULV, OPT. MATL, ROUND 24" S/CD	LF	220		\$0.00
0430175130	PIPE CULV, OPT. MATL, ROUND, 30" S/CD	LF	1026		\$0.00
0430175218	PIPE CULV, OPT. MATL, OTHER 18" S/CD	LF	398		\$0.00
0440 1 10	UNDERDRAIN, TYPE I	LF	591		\$0.00
0520 1 10	CONCRETE CURB & GUTTER, TYPE F	LF	5915		\$0.00
0520 2 2	CONCRETE CURB, TYPE B	LF	425.9		\$0.00
0520 2 4	CONCRETE CURB, TYPE D	LF	4320		\$0.00
0520 2 8	CONCRETE CURB, TYPE RA	LF	301.8		\$0.00
0522 1	SIDEWALK CONC, 4" THICK	SY	3496		\$0.00
0522 2	SIDEWALK CONC, 6" THICK	SY	176		\$0.00
0526 1 1-A	PAVERS, ARCHITECTURAL, TRUCK APRON	SY	250.2		\$0.00
0526 1 1-B	PAVERS, ARCHITECTURAL, SPLITTER ISLANDS	SY	135		\$0.00
0526 1 1-C	PERVIOUS PAVERS, ARCHITECTURAL, PARKING	SY	557		\$0.00
550 10 228	FENCING, TYPE B, 5.1-6.0, RESET EXISTING	LF	280		\$0.00
550 60 223	FENCE GATE, TYPE B, DOUBLE, 12.1-18.0' OPENING	EA	1		\$0.00
0527 2	DETECTABLE WARNINGS	SF	328		\$0.00
0570 1 2	PERFORMANCE TURF, SOD	SY	533		\$0.00
BIO-S.	BIOSWALES (WATER QUALITY SYSTEM)	EA	5		\$0.00
<b>Signing and Marking</b>					
0523 1 3	PATTERNED PAVEMENT, VEHICULAR AREAS, GREEN BIKE LANE	SY	744		\$0.00
0700 1 11	SINGLE POST SIGN, F&I, LESS THAN 12 SF	AS	39		\$0.00
0700 1 50	SINGLE POST SIGN, RELOCATE	AS	3		\$0.00
0700 1 60	SINGLE POST SIGN, REMOVE	AS	1		\$0.00
0706 3	RETRO-REFLECTIVE PAVEMENT MARKERS	EA	142		\$0.00
0711 11123	THERMOPLASTIC, STD, WHITE, SOLID, 12"	LF	2026		\$0.00
0711 11124	THERMOPLASTIC, STD, WHITE, SOLID, 18"	LF	30		\$0.00
0711 11125	THERMOPLASTIC, STD, WHITE, SOLID, 24"	LF	2201		\$0.00
0711 11141	THERMOPLASTIC, STD, WHITE, 2-4 DOTTED GUIDELINE / 6-10 DOTTED EXTENSION LINE, 6"	GM	0.769		\$0.00
0711 11160	THERMOPLASTIC, STD, WHITE, MESSAGE	EA	8		\$0.00
0711 11170	THERMOPLASTIC, STD, WHITE, ARROW	EA	19		\$0.00
0711 11180	THERMOPLASTIC, STD, WHITE, YIELD LINE	LF	111		\$0.00
0711 11224	THERMOPLASTIC, STD, YELLOW, SOLID, 18"	LF	149		\$0.00
0711 11241	THERMOPLASTIC, STD, YELLOW, 2-4 DOTTED GUIDELINE / 6-10 DOTTED EXTENSION LINE, 6"	GM	0.129		\$0.00
0711 11421	THERMOPLASTIC, STD, BLUE, SOLID, 6"	LF	56		\$0.00
0711 14160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	22		\$0.00
0711 14170	THERMOPLASTIC, PREFORMED, WHITE, ARROWS	EA	21		\$0.00
0711 16101	THERMOPLASTIC, STD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.615		\$0.00
0711 16102	THERMOPLASTIC, STD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.047		\$0.00
0711 16131	THERMOPLASTIC, STD-OTHER SURFACES, WHITE, SKIP, 6"	GM	0.03		\$0.00
0711 16201	THERMOPLASTIC, STD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.093		\$0.00

Attachment A

CITY OF NAPLES / COLLIER COUNTY  
CENTRAL AVENUE IMPROVEMENTS PROJECT

BID TABULATION FORM  
BID NO. << >>

0711 16202	THERMOPLASTIC, STD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.02		\$0.00
<b>Signalization</b>					
0630 2 11	CONDUIT, F&I, OPEN TRENCH	LF	750		\$0.00
0630 2 12	CONDUIT, F&I, DIRECTIONAL BORE	LF	275		\$0.00
0632 7 1	SIGNAL CABLE, FURNISH & INSTALL	PI	1		\$0.00
0635 2 11	PULL & SPLICE BOX, F&I, 13"X24" COVER SIZE	EA	14		\$0.00
0641 2 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL, POLE 30' & GREATER	EA	1		\$0.00
0646 1 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	2		\$0.00
0646 1 60	ALUMINUM SIGNALS POLE, REMOVE	EA	2		\$0.00
0649 31102	MAST ARM, F&I, WIND SPEED-150, SINGLE ARM, W/O LUMINAIRE - 46	EA	1		\$0.00
0649 31108	MAST ARM, F&I, WIND SPEED-150, SINGLE ARM, WITH LUMINAIRE - 60	EA	1		\$0.00
0649 36300	MAST ARM, REMOVE SHALLOW FOUNDATION, BOLT ON ATTACHMENT	EA	2		\$0.00
0650 1 14	TRAFFIC SIGNAL, F&I, 3 SECTION, 1 WAY, ALUMINUM	AS	6		\$0.00
0650 1 18	TRAFFIC SIGNAL, F&I, 5 SECTION STRAIGHT, 1 WAY, ALUMINUM	AS	1		\$0.00
0650 1 70	TRAFFIC SIGNAL, RELOCATE	AS	2		\$0.00
0653 1 12	PEDESTRIAN SIGNAL, F&I, LED COUNTDOWN, 2 WAY	AS	2		\$0.00
0660 2 102	LOOP ASSEMBLY, F&I, TYPE B	AS	12		\$0.00
0660 2 106	LOOP ASSEMBLY, F&I, TYPE F	AS	9		\$0.00
0665 1 11	PEDESTRIAN DETECTOR, F&I, STANDARD	EA	3		\$0.00
0670 5400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1		\$0.00
0682 1 400	ITS CCTV CAMERA, RELOCATE	EA	1		\$0.00
0700 5 22	INTERNALLY ILLUMINATED SIGN, F&I, OVERHEAD MOUNT, 12-18 SF	EA	2		\$0.00
<b>Lighting</b>					
0630 2 11	CONDUIT, F&I, OPEN TRENCH	LF	3525		\$0.00
0630 2 12	CONDUIT, F&I, DIRECTIONAL BORE	LF	1505		\$0.00
0635 2 11	PULL & SPLICE BOX, F&I, 13"X24" COVER SIZE	EA	42		\$0.00
0715 1 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 8-6	LF	19540		\$0.00
0715 1 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 4-2	LF	160		\$0.00
0715 1 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	1395		\$0.00
0715 7 11	LOAD CENTER, F&I SECONDARY VOLTAGE	EA	1		\$0.00
0715 11 118	LUMINAIRE, F&I, ROADWAY, FLOOD	EA	4		\$0.00
0715-516-115	LIGHT POLE COMPLETE-SPECIAL DESIGN, F&I, POLE TOP MOUNT, ALUMINUM, CUSTOM HEIGHT	EA	31		\$0.00
0715-540-000	LIGHT POLE COMPLETE-SPECIAL DESIGN, RELOCATE	EA	5		\$0.00
0715-550-000	LIGHT POLE COMPLETE-SPECIAL DESIGN, REMOVE	EA	3		\$0.00
<b>Utilities</b>					
1050 11222	2-4.9" PVC Pipe (F&I) - PROPOSED 2" & 4"	LF	125		\$0.00
1050 11223	5-7.9" PVC Pipe (F&I) - PROPOSED 6"	LF	625		\$0.00
1050 11224	8-19.9" PVC Pipe (F&I) - PROPOSED 8", 12", 16", 18"	LF	2010		\$0.00
1050 11424	8-19.9" DI PIPE (F&I) - PROPOSED 8"	LF	80		\$0.00
1050 11324	8-19.9" PE Pipe (F&I) - PROPOSED 10" (Directional Drill)	LF	375		\$0.00
1050 18002	2-4.9" Plug & Out of Service - 2" & 4"	LF	1021		\$0.00
1050 18003	5-7.9" Plug & Out of Service - 6"	LF	1235		\$0.00
1050 18004	8-19.9" Plug & Out of Service - 16"	LF	120		\$0.00
1080 11207	UTILITY FIXTURES, F&I, 2-4.9", LINE STOP	EA	1		\$0.00
1080 11307	UTILITY FIXTURES, F&I, 5-7.9", LINE STOP	EA	4		\$0.00
1080 11407	UTILITY FIXTURES, F&I, 8-19.9", LINE STOP	EA	3		\$0.00
1055 11414	UTILITY FITTING, F&I, DI/CI, ELBOW, 8-19.9"	EA	65		\$0.00
1055 11424	UTILITY FITTINGS, F&I, DI/CI, TEE, 8 - 19.9"	EA	17		\$0.00
1055 11454	8-19" UTILITY FITTINGS (F&I) PLUG/CAP	EA	2		\$0.00
1080 11404	UTIL FIXT, F&I, 8-19.9", VALVE ASSEMBLY	EA	32		\$0.00
1080 11409	UTIL FIXT, F&I, 8-19.9", MECH JONT RESTR	EA	260		\$0.00
1644113 08	FIRE HYDRANT, F&I, STD, 2 HOSE, 1 PUMP, 6"	EA	5		\$0.00
-	Long Water Services	EA	8		\$0.00
-	Short Water Services	EA	10		\$0.00
<b>Landscaping</b>					
<b>SINGLE TRUNK PALMS - LARGE PLANTS</b>					
580-1-2	ARCHONTOPHOENIX CUNNINGHAMIANA (PICCABEEN PALM)	EA	29		\$0.00
580-1-2	ROYSTONEA REGIA (ROYAL PALM)	EA	63		\$0.00
580-1-2	ADONIDIA MERRILLII (CHRISTMAS PALM)	EA	45		\$0.00
<b>TREES - LARGE PLANS</b>					
580-1-2	QUERCUS VIRGINIANA 'HIGH RISE' (HIGH RISE SOUTHERN LIVE OAK)	EA	17		\$0.00
580-1-2	TAXODIUM DISTICHUM (BALD CYPRESS)	EA	9		\$0.00
<b>SHRUBS - SMALL AND LARGE PLANTS</b>					
580-1-2	CHRYSOBALANUS ICACO 'RED TIP' (RED TIP COCOPLUM)	EA	232		\$0.00
580-1-1	DIANELLA TASMANICA 'VARIEGATA' (FLAX LILY)	EA	675		\$0.00
580-1-1	IXORA COCCINEA 'NORA GRANT' (RED IXORA)	EA	692		\$0.00
580-1-1	SCHEFFLERA ARBORICOLA 'TRINETTE' (VARIEGATED SCHEFFLERA)	EA	505		\$0.00
580-1-1	DURANTA REPANS 'GOLD MOUND' (GOLDEN DEWDROP DURANTA)	EA	101		\$0.00
580-1-1	FICUS MICROCARPA 'GREEN ISLAND' (GREEN ISLAND FICUS)	EA	3019		\$0.00
580-1-1	JUNIPERUS CHINENSIS 'PARSONII' (CHINESE JUNIPER)	EA	488		\$0.00
580-1-1	NEOREGELIA X 'ROYAL BURGANDY' (ROYAL BURGANDY BROMELIAD)	EA	186		\$0.00
<b>ANNUALS</b>					
580-1-1	ANNUALS	EA	308		\$0.00

Attachment A

CITY OF NAPLES / COLLIER COUNTY  
CENTRAL AVENUE IMPROVEMENTS PROJECT

BID TABULATION FORM  
BID NO. << >>

ORNAMENTAL GRASSES - SMALL PLANTS					
580-1-1	MUHLENBERGIA CAPILLARIS(PINK MUHLY)	EA	503		\$0.00
580-1-1	SPARTINA BAKERI(SAND CORD GRASS)	EA	156		\$0.00
<b>SOIL AMENDMENTS</b>					
-	BOLD & GOLD	CY	48		\$0.00
<b>Irrigation</b>					
0590 70	IRRIGATION SYSTEM	LS	1		\$0.00

CONTRACTOR NAME: \_\_\_\_\_  
PRINT / SIGN / DATE

<b>SUBTOTAL:</b>	\$0.00
<b>2.5% ALLOWANCE:</b>	\$0.00
<b>PROJECT TOTAL:</b>	<b>\$0.00</b>