



Florida Department of Environmental Protection

Rick Scott
Governor

Carlos Lopez-Cantera
Lt. Governor

South District
Post Office Box 2549
Fort Myers, Florida 33902-2549
SouthDistrict@dep.state.fl.us

Jonathan P. Steverson
Secretary

Notification of Acceptance of Use of a General Permit

Permittee:

City of Naples
Allyson Holland, P.E., Deputy Utilities
Director
380 Riverside Circle
Naples, FL 34102

Emailed to: amholland@naplesgov.com

Permit Number: 339301-001-DSGP

Issue Date: November 20, 2015

Expiration Date: November 19, 2020

County: Collier

Project Name: Central Avenue Water
Main Improvements

Water Supplier: City of Naples WTP

PWS ID: 5110198

Dear Ms. Holland:

On November 4, 2015, the Florida Department of Environmental Protection received a "Notice of Intent to Use the General Permit for Construction of Water Main Extensions for PWSs", [DEP Form No. [62-555.900\(7\)](#)], under the provisions of Rule [62-4.530](#), and Chapter [62-555](#), Florida Administrative Code (F.A.C.). The proposed project includes the installation of 27 Linear Feet (LF) of 3-inch PVC Water Main (WM), 800 LF of 6-inch PVC WM, 2,092 LF of 8-inch PVC WM, 155 LF of 10-inch HDPE (Directional Drilled) and 120 LF of 16-inch PVC WM.

Based upon the submitted Notice and accompanying documentation, this correspondence is being sent to advise that the Department does not object to the use of such general permit at this time. Please be advised that the permittee is required to abide by Rule [62-555.405](#), F.A.C., all applicable rules in Chapters [62-4](#), [62-550](#), [62-555](#), F.A.C., and the General Conditions for All General Drinking Water Permits (found in [62-4.540](#), F.A.C.).

When any existing asbestos cement (AC) pipes are replaced under this permit, the permittee shall do so in accordance with the applicable rules of the Federal Asbestos Regulation and Florida DEP requirements. For specific requirements applicable to AC pipes, the permittee should contact the Air and Waste Management section managers prior to commencing any such activities at (239) 344-5600. Please be aware that a notification is required to be submitted to the Department for a regulated project.

The permittee shall comply with all sampling requirements specific to this project. These requirements are attached for review and implementation.

Pursuant to Rule [62-555.345](#), F.A.C., the permittee shall submit a certification of construction completion [DEP Form No. [62-555.900\(9\)](#)] to the Department and obtain approval, or clearance,

Permittee: City of Naples
Allyson Holland, P.E., Deputy Utilities Director
Page 2 of 2

PWS ID 5110198


Permit No. 339301-001-DSGP

from the Department before placing any water main extension constructed under this general permit into operation for any purpose other than disinfection or testing for leaks.

Within 30 days after the sale or legal transfer of ownership of the permitted project that has not been cleared for service in total by the Department, both the permittee and the proposed permittee shall sign and submit an application for transfer of the permit using Form 62-555.900(8), F.A.C., with the appropriate fee. The permitted construction is not authorized past the 30-day period unless the permit has been transferred.

This permit will expire five years from the date of issuance. If the project has been started and not completed by that time, a new permit must be obtained before the expiration date in order to continue work on the project, per Rule 62-4.030, F.A.C.

Sincerely,



Megan Mills
Permitting Program Administrator

MM/JR/se

cc: W. Wade Wood, III, P.E. wade.wood@kimley-horn.com

Attachment

**A Civil Penalty May Be Incurred
if this project is placed into operation before obtaining a clearance from this office.**

Requirements for clearance upon completion of projects are as follows:

1) Clearance Form

Submission of a fully completed Department of Environmental Protection (DEP) Form [62-555.900\(9\)](#), *Certification of Construction Completion and Request for Clearance to Place Permitted PWS Components into Operation*.

2) Record Drawings, if deviations were made

Submission of the portion of record drawings showing deviations from the DEP construction permit, including preliminary design report or drawings and specifications, if there are any deviations from said permit (Note that it is necessary to submit a copy of only the portion of record drawings showing deviations and not a complete set of record drawings.).

3) Bacteriological Results

Copies of satisfactory bacteriological analysis (a.k.a. Main Clearance), taken within sixty (60) days of completion of construction, from locations within the distribution system or water main extension to be cleared, in accordance with Rules 62-555.315(6), 62-555.340, and 62-555.330, F.A.C. and American Water Works Association (AWWA) Standard C 651-92, as follows:

- Connection to an existing system
- The end point of the proposed addition
- Any water lines branching off a main extension
- Every 1,200 feet on straight runs of pipe

Each location shall be sampled on two consecutive days, with sample points and chlorine residual readings clearly indicated on the report. A sketch or description of all bacteriological sampling locations must also be provided.

4) Pressure Test Results

Copy of satisfactory pressure test results demonstrating compliance with AWWA Standard requirements.

For further clarification contact: Juan Robles;
2295 Victoria Avenue, Suite 364, Fort Myers, FL 33901; (239) 344-5660 and/or
E-mail: Juan.Robles@dep.state.fl.us