

**CITY OF NAPLES
PURCHASING DIVISION
CITY HALL, 735 8TH STREET SOUTH
NAPLES, FLORIDA 34102
PH: 239-213-7100 FX: 239-213-7105**

ADDENDUM NUMBER 4

NOTIFICATION DATE:	BID TITLE:	BID NUMBER:	BID OPENING DATE & TIME:
02/24/16	Utilities Maintenance Building Replacement	16-022	03/01/2016 2:00PM

**THE FOLLOWING INFORMATION IS HEREBY INCORPORATED INTO,
AND MADE AN OFFICIAL PART OF THE ABOVE REFERENCED BID.**

The following clarifications are issued as an addendum for the referenced solicitation:

Below are responses to submitted written questions.

- 1) Please provide direction on handling the electric alternates on sheets E-002 and E-301.
Reissue bid form with following alternates.
- A. Base Bid - Future Genset / Alternate Bid - Install O.F. Genset (will need product information) - Sheet E-301
 - B. Base Bid - Base Bid - Provide 3 2" PVC conduits to set pad / Alternate Bid - Provide general service conductors- 3-#3/0 Cu, 1-#1 Cu B in each run - Sheet E-301
 - C. Base Bid - Provide 1-2" PVC conduit to genset pad for accessory power requirements / Alternate Bid - Provide circuit wiring - Sheet E301
 - D. Base Bid - Provide generator docking station / Alternate bid - Eliminate generator docking station & feeders -Sheet E-301
 - E. Base Bid - Provide 1" PVC conduit for future gen control conductors / Alternate Bid - Provide all wiring for remote panel annunciator - Sheet E-002
 - F. Base Bid - Provide 1" PVC conduit for genset remote emergency stop / Alternate bid - Provide break glass type emergency stop station & required wiring - Sheet E-002

Answer - Drawings E-002 and E-301, REVISE, All language noted as alternate bid items related to the Generator (2 locations on E-002 and 4 locations on E-301) be revised such that the described Alternate bid and Base bid items are INCLUDED in the Base bid and the alternate is eliminated as a alternate bid item now a part of the base bid.

- 2) Is concrete strength 3000 PSI or 4000 psi? Two specifications see sheet S1.0 and sheet A-800.

Answer: MODIFICATIONS TO THE DRAWINGS

Drawing A-800 – Section 03300 – Cast In Place Concrete, Item 2, Revise 3,000 to 4,000.

IMPORTANT MESSAGE

PLEASE ACKNOWLEDGE RECEIPT OF THIS ADDENDUM ON THE BID COVER SHEET.

3) Verify acoustical ceiling specification, see RCP note 1 on sheet A-203 or under spec section 09510 on sheet A-803.

Answer: MODIFICATIONS TO THE DRAWINGS

Drawing A-803 – Section 09510 – Acoustical Ceilings, Item 3. B. 2 Revise Ceiling type to be #1756.

4) Please clarify the PEMB siding and roof panel profiles.

Answer: MODIFICATIONS TO THE DRAWINGS

Drawing A-803 – Section 13122 – Metal Building Specification, Revise Item 3., C and D. to Wall and Roof panels shall be MBCI – Storm Proof profile or equivalent.

5) Are clarifications acceptable to submit with the bid or is that grounds for rejection?

Answer: All clarification should be resolved prior to submission. Please review General Conditions, Sec 41 Exceptions.

6) On the "Submission Checklist" sheet the second row lists 10 - 11 items, are all of these items to be submitted with the bid (mandatory) and if so where do I find the "questionnaire", "forms", "tabs", "price/cost", "product compliance/exception" forms.

Answer: The check list is to indicate inclusion. Please mark if any such items are included in your response which is required in the bid document.

#

IMPORTANT MESSAGE

PLEASE ACKNOWLEDGE RECEIPT OF THIS ADDENDUM ON THE BID COVER SHEET.