

**CITY OF NAPLES  
PURCHASING DIVISION  
CITY HALL, 735 8<sup>TH</sup> STREET SOUTH  
NAPLES, FLORIDA 34102  
PH: 239-213-7100    FX: 239-213-7105**

**ADDENDUM NUMBER 1**

NOTIFICATION DATE:	SOLICITATION TITLE:	SOLICITATION NUMBER:	BID OPENING DATE & TIME:
<b>4/20/2022</b>	<b>Anthony Park Dock Replacement - FWQ</b>	<b>22-029</b>	<b>4/22/2022 2:00PM</b>

**THE FOLLOWING INFORMATION IS HEREBY INCORPORATED INTO,  
AND MADE AN OFFICIAL PART OF THE ABOVE REFERENCED BID.**

The following clarification is issued as an addendum identifying the following change for the referenced solicitation.

Q. It says deck stringers are to be replaced but does not state the size required (2x12)?

A. **The stringers are 2x12.**

Q. Also, will a double stringer be necessary for the outer band/stringer?

A. **A double stringer is not necessary on the outer band.**

Q. Page 2/under Notes/#8 States "Once Work begins the contractor must be on site every day until completion"- Does that include weekends as well?

A. **Working hours are Mon-Friday from 7:00am -5:00pm. No weekend work.**

Q. Is there any designated lay down area for this project. Can we just put some kind of fence around the entrance to the dock to keep materials there?

A. **Yes-you can use an area near the dock, or in the parking area whichever preferred and just secure the area with some type of fencing.**

Q. What kind of equipment allowed (weight wise) on the park circle road leading to the dock?

A. **We drive our F-450 trucks to the back without issue. So nothing bigger than an F-450 (or equivalent).**

Q. There is a note for stringers to be "installed a minimum of 16"o.c.". This would be maximum correct?

A. **16" maximum.**

**IMPORTANT MESSAGE**

**PLEASE ACKNOWLEDGE RECEIPT OF THIS ADDENDUM ON THE BID COVER SHEET .**