

**CITY OF NAPLES
PURCHASING DIVISION
CITY HALL, 735 8TH STREET SOUTH
NAPLES, FLORIDA 34102
PH: 239-213-7100 FX: 239-213-7105**

ADDENDUM NUMBER 1

NOTIFICATION DATE:	BID TITLE:	BID NUMBER:	BID OPENING DATE & TIME:
04/27/12	Ground Storage Tank Painting	042-12	05/08/12 2:00PM

**THE FOLLOWING INFORMATION IS HEREBY INCORPORATED INTO,
AND MADE AN OFFICIAL PART OF THE ABOVE REFERENCED BID.**

Questions:

1) *What is the contract duration and liquidated damages for this project?*

The work to be performed under this contract shall be commenced within ten (10) calendar days after date of Notice to Proceed and shall be substantially completed within 90 calendar days after the date of this Notice to Proceed, and shall be finally completed within 30 calendar days after the date of substantial completion.

Once the Contractor has mobilized to a project site (Solana, East Naples, or Port Royal) the Contractor must be complete with all the specified work at the project site within thirty (30) calendar days.

2) Also will the tanks be taken out of service while being cleaned and painted?

The two 1 MG tanks at East Naples will be off-line for the project; all others will be in operation.

3) Can we work on multiple tanks at one time?

Yes

IMPORTANT MESSAGE

PLEASE ACKNOWLEDGE RECEIPT OF THIS ADDENDUM ON THE BID COVER SHEET.

Comments:

- 1) The costs associated bid item "Port Royal 0.5 MG Tanks" shall include the complete removal of the existing coatings on the exterior of the tanks; down to bare concrete.
- 2) The costs associated bid item "Port Royal Building" shall include the removal and replacement of the north, east, and south stucco surfaces of the exterior of the generator enclosure. The new stucco surfaces shall be installed the full height of the generator enclosure walls and shall include flashing, corner bead, expansion joints, and bonding agents to prevent future water intrusion behind the stucco finish.
- 3) The cleaning and removal of old coatings from all tank surfaces shall require minimum 3500 psi pressure washing. The pressure washer(s) used by the Contractor must be able to meet this requirement.
- 4) The costs associated bid item "Solana Building" shall include the retention wall that surrounds the generator. The surface area for these walls is approximately 500 square feet. Preparation will include power washing and a fresh water rinse followed by the application of two coats of Tnemec Series #6 Tneme-Cryl at 2.0 mils per coat (approximately 345 sq. ft. per gallon).

IMPORTANT MESSAGE

PLEASE ACKNOWLEDGE RECEIPT OF THIS ADDENDUM ON THE BID COVER SHEET.